

# STRONGPOST® FLOOR JOIST SYSTEM NOT TO SCALE

#### NOTES:


- GROUND TO BE AS SMOOTH AND LEVEL AS POSSIBLE.
- DEPENDING UPON THE RESULTS OF THE SITE ASSESSMENT, IMPLEMENT THE POLYBASE ® FOUNDATION PLAN ACCORDINGLY.
- CONSULT STRONGPOST® SYSTEM PIPE LOAD CHART FOR PIPE CAPACITIES
- THERE IS AN ALLOWABLE PRESUMPTIVE DESIGN SOIL BEARING PRESSURE OF 2,000 PSF. IF WEAKER SOIL CONDITIONS ARE ENCOUNTERED, EXTEND THE FOOTING TO A SUITABLE MATERIAL OR CONSULT A CERTIFIED PROFESSIONAL.
- STRONGPOST® IS INTENDED TO PROVIDE ADDITIONAL SUPPORT TO EXISTING FRAMING. NO LIFTING IS ANTICIPATED.



**DETAILS** 

2.875"Ø PIPE CROSS-SECTION





## STRONGPOST® FLOOR JOIST SYSTEM WITH STONE PAD

#### NOTES:


- GROUND TO BE AS SMOOTH AND LEVEL AS POSSIBLE.
- DEPENDING UPON THE RESULTS OF THE SITE ASSESSMENT, IMPLEMENT THE POLYBASE ® FOUNDATION PLAN ACCORDINGLY.
- CONSULT STRONGPOST® SYSTEM PIPE LOAD CHART FOR PIPE CAPACITIES
- THERE IS AN ALLOWABLE PRESUMPTIVE DESIGN SOIL BEARING PRESSURE OF 2,000 PSF. IF WEAKER SOIL CONDITIONS ARE ENCOUNTERED, EXTEND THE FOOTING TO A SUITABLE MATERIAL OR CONSULT A CERTIFIED PROFESSIONAL.
- STRONGPOST® IS INTENDED TO PROVIDE ADDITIONAL SUPPORT TO EXISTING FRAMING. NO LIFTING IS ANTICIPATED.



**DETAILS** 

2.875"Ø PIPE CROSS-SECTION





### STRONGPOST® FLOOR JOIST SYSTEM WITH CIP PAD

NOT TO SCALE

#### NOTES:

- DEPENDING UPON THE RESULTS OF THE SITE ASSESSMENT, INSTALL CONCRETE FOOTING AS PER THE ENGINEER OF RECORD.
- DEPENDING UPON THE RESULTS OF THE SITE
   ASSESSMENT, IMPLEMENT THE STEEL BASE MOUNT
   ACCORDINGLY.
- 3. CONSULT STRONGPOST ® SYSTEM PIPE LOAD CHART FOR PIPE CAPACITIES
- 4. THERE IS AN ALLOWABLE PRESUMPTIVE DESIGN SOIL BEARING PRESSURE OF 2,000 PSF. IF WEAKER SOIL CONDITIONS ARE ENCOUNTERED, EXTEND THE FOOTING TO A SUITABLE MATERIAL OR CONSULT A CERTIFIED PROFESSIONAL.
- STRONGPOST® IS INTENDED TO PROVIDE ADDITIONAL SUPPORT TO EXISTING FRAMING. NO LIFTING IS ANTICIPATED.



**DETAILS** 

STRONGPOST JOIST SYSTEM

2.875"Ø PIPE CROSS-SECTION

OF 3
ISSUE DATE:
03/05/24
PROJECT NO:
Z17-0012